#### Exceptional service in the national interest







### Truck Transport Results / Progress on Rail Test

5NL-BAM Workshop 7 October 2014 Paul McConnell SAND2014-18948 PE






#### What we think we know



- The strains measured in the test program were in the micro-strain levels – well below the elastic limit for either unirradiated or irradiated Zircaloy-4.
- Based upon the test results, which simulated normal vibration and shock conditions of truck transport, strain- or stress-based failure of fuel rods during normal transport seems unlikely.
- Strains on irradiated rods may be less than strains measured on unirradiated tubes.
- Normal conditions of truck transport are more severe than rail.

#### **ISFSI Locations**





http://www.enviroreporter.com/wp-content/uploads/2013/10/NRC-map-of-Independent-Spent-Fuel-Storage-Installations.jpg



### Lots of Assemblies to be Stored & Transported

Fuel Cycle Potential Waste Inventory for Disposition July 2012






Figure 3-3 Cumulative UNF Assemblies Discharged for the No Replacement, Maintain Current, 200 GWe/yr, and 400 GWe/yr.

### **Transportation**







Courtesy Yankee Rowe



Heavy-haul truck required to get to railhead
Courtesy Yankee Rowe



Hoosac Tunnel
See: http://en.wikipedia.org/wiki/Hoosac\_Tunnel

Yankee Rowe

#### **Transportation**








Parking lot for heavy-haul truck access to railhead!





### **Central Storage Facility**






http://www.world-nuclear-news.org/WR-Rethink\_on\_Utah\_used\_fuel\_storage\_project-0408104.html


## Repository





### **Not** a Repository







#### There Will Be Lots of High Burnup Assemblies




Figure 3-7 Percentage of Assemblies per Burn-up Range - Maintain Current Nuclear Generation Case


### Motivation for assembly testing



- Federal Regulations require an assessment of
   "Vibration Vibration normally incident to transport"...
   ...imposed on transport packages and contents during "normal conditions of transport". (10CFR71.71)
- The NRC has approved normal transport of low burnup spent fuel.
- However, the technical community needs to <u>establish a technical</u> <u>basis</u> to demonstrate that <u>high burnup fuel rods</u> can withstand all normal conditions of transport.
- Vibrations and shocks have been measured on truck trailers and railcars <u>but not directly on fuel assemblies</u>, <u>baskets</u>, <u>or fuel rods</u>.



# In other words, could Zircaloy cladding fracture during normal conditions of transport?



http://sanonofresafety.org/nuclear-waste/

### **Application of Fuel Assembly Test Results (1)**



The margin of safety between the applied loads on fuel rods during transport and the material properties of Zircaloy rods has not been quantified.


The SNL assembly tests provide data – the applied stresses on the rods

- related to the issue of the margin of safety:

applied rod stress<sub>normal transport</sub>

Material property test programs at other national laboratories shall measure properties of high burnup cladding:


yield strength<sub>cladding</sub>





### **Application of Fuel Assembly Test Results (2)**


- The data from the assembly tests will be used to validate finite element models of fuel assemblies.
- The validated models can be used to predict the loads on fuel rods for other basket configurations and transport environments, particularly rail.



FUEL ASSEMBLY SHAKER TEST SIMULATION, Klymyshyn, et al., PNNL, FCRD-UFD-2013-000168, May 2013



### **SNL Experimental 17x17 PWR Assembly**



Only Zircaloy rods were instrumented with strain gauges and accelerometers

Isometric View of Fuel Rods (Top Nozzle and Basket not shown)

### **Basket/Assembly Test Unit**



- The test unit included an assembly and a basket.
- The basket is based upon the geometry of the NAC-LWT truck cask PWR basket.
- The assembly was placed in a basket which was placed on 1) a shaker and subsequently 2) a truck trailer.

The assembly had the same freedom of motion within the basket as

it would have in an actual cask.

- 6061 Aluminum Basket
- Sides 1.5 inches thick
- Top/bottom 1 inch thick
- Length 161.5 inches
- Weight 837 pounds




# Lead Rod within Copper Tube to Simulate Mass of UO<sub>2</sub> (Zircaloy-4 tubes also contained Lead)






# Uniaxial Accelerometer and Strain Gauge Carbonal Caboratories on Test Assembly



Left: Accelerometers and Strain Gauge on Top-Center Zircaloy Tube and Spacer Grid



Right: Assembly within Open Basket. Note the two Zircaloy-4 rods with instrumentation attached






### **Shaker Shock Test Video**



Top-end view of assembly in basket



### during Shaker Shock Test – Strains are very low



M				
Rod Location	Assembly Span	Position on Span	Maximum Strain (μin./in.)	
Top-middle rod	Bottom-end	Adjacent to spacer grid	90	
Top-middle rod	Bottom-end	Mid-span	131	
Top-middle rod	Bottom-end	Adjacent to spacer grid	171	
Top-middle rod	Mid-assembly	Adjacent to spacer grid	104	
Top-middle rod	Mid-assembly	Mid-span	97	
Top-middle rod	Top-end	Adjacent to spacer grid	127	
Top-middle rod	Top-end	Mid-span	199 🗲	— maximum
Top-middle rod	Top-end	Adjacent to spacer grid	70	
Top-side rod	Bottom-end	Adjacent to spacer grid	54	
Top-side rod	Bottom-end	Mid-span	107	
Top-side rod	Top-end	Mid-span	117	
Top-side rod	Top-end	Adjacent to spacer grid	113	
Bottom-side rod	Bottom-end	Mid-span	62	
Bottom-side rod	Bottom-end	Adjacent to spacer grid	121	
Bottom-side rod	Mid-assembly	Adjacent to spacer grid	110	
Bottom-side rod	Mid-assembly	Mid-span	115	
	Λνος	age of All Strain Gages	112	<ul><li>average</li></ul>
	AVCI		124	_
		Average Top-middle Rod	98	maximum
		Average Top-side Rod	102	
Average Bottom-side Rod			105	
Average Bottom-end Span			107	
Average Mid-assembly Span  Average Top-end Span			125	
			118	
Average Mid span				
	A	verage Adjacent to Spacer Grid	107	
				21




## **Test Unit on Concrete Blocks on Trailer**



# Truck Test Route 65 km in Albuquerque area





## **Range of Road Conditions**







## Route included railroad crossings...






## ...and rough dirt roads






### Strains measured on instrumented rod









### **Strains correlated to road surfaces**








# Rod Strains and FFT maximum strains occurred at low Hz



# Side Basket Showing Cutout for Filming Assembly during Truck Test







#### **Langweilig** Video of Assembly during the Truck Test



# Maximum Strains Measured during Truck Test in similar to shaker results




Strain Gauge	Location on Assembly	Maximum Micro-strain Absolute Value (μin./in.)	Road Segment
S1 - 0°		55	
S1 - 90°	Adjacent to first spacer grid, Span 10	53	
S1 - 225°		74	P. C. S.
			The same of the sa
S2 - 0°		94	
S2 - 90°	Mid-span, Span 10	99	
S2 - 225°		86	
		<b>X</b> = 10 m	
S3 - 0°		143	
S3 - 90°	Adjacent to first spacer grid, Span 5	84	
S3 - 225°		108	
S4 - 0°		69	The second second
S4 - 90°	Mid-span, Span 5	101	
S4 - 225°		93	
Average 0°		90	
Average 90°		83	1
Average 225°		90	

All maximum strains during road Segment #1 at 872.4 – 902.3 seconds into the trip. This corresponds to travel on Poleline Road (dirt).

# Measured Strains are Very Low Relative to the Elastic Limit of Zircaloy-4





# Irradiated rods would experience lower strains during truck test than unirradiated tube



Bending stiffness (=EI) of high burnup irradiated Zircaloy-4 with pellet-clad interaction (per ORNL):

$$EI_{Zirc4-irr} = 52 \text{ N-m}^2$$
 (I based upon rod geometry)  
 $E_{Zirc4-irr} = 83 - 101 \text{ GPa}$ 

Bending stiffness of unirradiated Zircaloy-4 tube:

$$EI_{Zirc4-unirr} = 15.9 \text{ N-m}^2$$
 (I based upon tube geometry)  
 $E_{Zirc4-unirr} = 99 \text{ GPa}$ 

Bending stiffness Zircaloy-4 (irradiated rod/unirradiated tube) = 52/15.9 = 3.27

This implies that for a given applied moment, strains on an irradiated rod would be approximately 0.3 (1/3.27) of those on an unirradiated Zircaloy-4 tube.


The maximum strain measured on the Zircaloy-4 tube in the truck test was 147µm/m, so for the same applied loads, the strain on an irradiated rod would be:

$$147(15.9/52) = 45 \mu m/m$$

### Rail Test Options



#### TN-32 cask transport from Pennsylvania to North Carolina



## **Rail Test Options**



NLI-10/24 cask tests at Tri-City Railroad near PNNL





Augusta, Georgia

## **TCRY Railyard**

Richland, Washington










38

#### Shock Response Spectrum NUREG CR-0128 vs. P1 and P3 Shock Vertical Load Cases



## Rail loadings less severe than truck loads





(b) Vibration

# Fracture Mechanics & Fatigue Assessments Based Upon Experimentally-Measured Strains



