

Exceptional service in the national interest

Investigation of Installation Practices: Field Observations

Sandia-EPRI Connector Reliability Workshop

Bruce King

July 17, 2024













SAND2024-9131C



"Connector Reliability Across the US Solar Sector"




Site Visits: Utility, Commercial, Small R&D

Goals & Outcomes:

- First-hand observations of installation practices, connector brand/model diversity and field failures
- Invaluable discussions with on-site O&M crews.
- Harvested connector samples returned to Sandia for evaluation
 - Beginnings of a database of field failure categories

Next few slides will provide a highlight of observations





Home-runs: Ferrules, torque and cable insulation









- Numerous examples of seal failures at the ferrule
- Evidence of cable insulation "pullout".....short stripping or shrinkage?
- Incipient cable corrosion in some cases
- Almost certainly accompanied by water ingress into housing
- Not a matter of "if"....a matter of "when"




Home Run Bundles: Thermal Damage and inspection challenges









- Runaway resistive heating at pinsleeve contact
- Bundled home run harnesses can put adjacent connectors at risk
- Emerging thermal damage may not be easy to identify
- Blocks with failed strings are offline...no current = no heat
- Identification by maintenance crews often most reliable






Dissecting a Failed Wiring Harness









Improper torque, poor insertion

Wrong Crimp Tool

Proper torque Collapsed strain relief Pin secure





Cut Strands Wrong strip tool?






Proper torque

Improper torque










Module Replacements/Cable Management









- Field-made jumper to accommodate a module replacement
- Cable routing left connectors laying in trays where they could be submerged
 - connectors are IP68, but....only if they're assembled correctly
- Electrical arc to racking



- Cross-mating between replacement modules
- Single module model, two j-box & connector assemblies
- In total, four different connectors observed on site
 - Original module high #'s
 - Replacement module low #'s
 - Home runs & harnesses med #'s
 - Field repair very low #'s



Summary

- Utility field inspections to date have revealed failures only in wiring harnesses or field made jumpers/replacements
 - → Considerable inconsistency in installation practices even within the same site
- Use of improper tools combined with improper assembly almost guarantees failure
 - → moisture ingress, corrosion and arcing
 - → high resistance points
- Cable management practices can exacerbate problems due to improper connector assembly
 - → routing through metallic cable trays provides an easy arc path to ground
 - → bundling in wiring harnesses can lead to collateral damage
- Installation of replacement modules can lead to inadvertent connector cross-mating